

PRICE BID					
ABSTRACT OF COST FOR PROPOSED INTERIOR WORK FOR CENTRAL BANK OF INDIA PREMISES FOR RAJAMPET BRANCH					
FURNISHING WORK					
Sl. No	Description of Item	Qty.	Rate	Per Unit	Amount (Rs)
1	<p>COUNTER WITH SIDE TABLE With Tempered Glass Top Size: - 5'-0" X 2'-6" Side Table Size: - 2'-6" X 1'-6" Providing & Fixing officer table & side table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table including side table shall be 2'-6". Depth of the table shall be 2'-6" & side table shall be 1'-6". The counter top to have 8mm thick tempered/toughened transparent glass, cut to size with edge rounding of all edges, including that on the side table. The counter top to have a 12mmthk PLAIN glass partition of 18" height, positioned 6" from Customer side of the Table Top. The top of glass to be straight cut and to have cut-out for transactions with Garware Film (Ice Dot) (Basic Cost Of Film Rs.36/- Per sft) fixed (at one inch from cut-out edge) as a border to semi-circular cut-out and top. The table shall have one drawer for key board at the corner of the table & side table. The luding all interconnections & accessories etc 5-1982) is then screw fixed to ceiling to ceiling section with 25mm drywait at 230mm centers. Screw fixing is done mechanically either with screwdriver of drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look, which includes filling with CRACK SEAL / tape & finishing the tapered & square edges of theboards with jointing compound, paper tape & two coats of primer suitable for Gypboard. Rate includes provision for recessed/dropped portion in the ceiling with necessary provision for concealed optical fibre lighting as per design specified by architect Note: - For light fittings, grills diffusers and cut-outs, speakers, fire detectors etc. have to be made with the frame of perimeter channels of size 20 X 27 X 30mm X0.545mm thick, supported suitably as per direction of Architect, Electric or A.C. Consultants & shown as per detail drawing without additional payments. Entire false ceiling shall be finish with 3 coats of ICI. Plastic Emulsion paint with necessary scraping, patti, levelling & smooth finish with scaffolding, cleaning etc. Note:- Area of the False Ceiling will be measured in plan i.e. wall to wall. Note: - Existing false ceiling should be removed without any extra charge by the Contractor and carefully stacked as directed / taken out from site.inclusive of making of the opening for the Electrical / Computer Wires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots. e Electrical / Computer Wires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots.</p>	4.00		Nos	
2	<p>CASH COUNTER Table With Tempered Glass Top Size: - 7'-0" X 2'-6" Side Table Size: - 3'-9" X 1'-6" Do as above ITEM NO.A01, but cash counter shall have 3'-0" height for customer top finish with 18" wide 20mm thick ruby red granite top, with 4" overhang on customer side, having 12mm thk PLAIN glass with Garware Film (Ice Dot) (Basic Cost Of Film Rs.36/- per sft) fixed between 3'-0" & 7'-0" in height with necessary cut-outs etc. complete as per instructions of Architect. Top covered with Aluminium Grill for safety and voucher tray to be provided on adjacent cubicle side of side partition as per site conditions. Side table to have 2 Drawers with currency dividers at the top and 1 open-able shelf at the bottom. All the exposed surfaces of the table & side table shall be finished in 1.00mm thick approved colour laminate for vertical surfaces and 1.5mm thk approved colour laminate for horizontal surfaces, made Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303 framework tapered box finish, Foot Rest luding all interconnections & accessories etc Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Architect.All exposed surfaces including working TOP of counter shall have decorative laminate. All exposed surfaces shall have 1.00mm thk approved colour laminate in two shades for vertical surfaces & approved colour 1.5mm thick laminate for horizontal surfaces. The internal surfaces shall have same finish including approved Single Lock for Drawer Units, approved Stainless Steel Brush Finish Handles, approved Brass Powder Coated Wire Manager, Twin Type Telescopic Drawer Channels, Footrest with Rubber Matting etc. complete as per instructions of Architect. The rates shall be inclusive of making of the opening for the Electrical / Computer Wires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots. Side table to have 2 Drawers at the top and 1 open-able shelf at the bottom. All the exposed surfaces of the table & side table shall be finished in 1.00mm thick approved colour laminate for vertical surfaces and 1.5mm thk approved colour laminate for horizontal surfaces, made Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303 framework tapered box finish, Foot Rest with Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Architect.</p>	1.00		NO.	

10	NOTICE BOARD - (3'-0" - 2'-0") Providing & Supplying notice board of 3" deep made out of C.P.T. Wood framing with 1/2" Soft Board covered with felt on 6mm thk Commercial ply (MR grade) IS303 for back & glass-shutters fixed with 3" X 1" C.P.T. Wood section finish with 1.00mm thk laminate of approved shade / make with open-able on approved brass hinges with Godrej lock & approved powder coated handle etc. complete as per instructions of Architect.	1.00		NO.	
11	12mm Thk MAIN GLASS DOOR - 6' wide DOUBLE leaf door WITH FIXED GLASS FOR REMAINING LENGTH ON EITHER SIDE OF ENTRANCE (WHEN FACING BRANCH) - DOUBLE leaf door with required 10mm Thk Fixed Glass with required Boxing all around Providing and Fixing 12mm thick Toughened glass main door with Garware Film (Ice Dot) (Basic Cost Rs.36/-Per SFT) or "V" cut engraving fixed in the frame work along with Brush Finish Stainless Steel 1" Dia 2'-0" Height approved design Handles with 8 Lever Locks, Pull & Push Plate, DORMA make Heavy Duty Floor Spring, etc. complete as per instructions of the Architect.	126.00		sft	
12	WRITING / CHALLAN DESK - 4'0"x 2'6" Providing & Fixing writing table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. Table shall be fixed at 3'-6". Depth of the table shall be 2'-6". The table shall have 6 compartments for challans of 6" height below the writing surface, as per Banks Standard Design	1.00		No.	
13	CHEQUE DROP BOX cum SUGGESTION BOX (2'-0" X 1'0") - It shall be made in 18mm thick Commercial ply (MR grade) IS303 frame work with 6mm thick Commercial ply (MR grade) IS303 back 3" X 1" C.P.T. Wood shutters with 6mm thick MODI make with hinges, locks & fixtures. The box to be divided into two portions such that one half serves as drop box, while the other serves as suggestion box, with shorter shutter to leave slot for dropping A4 sized envelope in each box. The approved shade/make 1.00mm thick laminate shall be fixed all exposed portion of the cabinet etc. complete as per site location & instructions of the Architect.	2.00		No.	
14	MIRROR SHELF - in locker room (7'-0" X 2'0") It shall be made in 18mm thick Commercial ply (MR grade) IS303 frame work with 6mm thick Commercial ply (MR grade) IS303 back 3" X 1" C.P.T. Wooden backing with high quality mirror fixing, with lighting all the top and sides having a cushioned stool of height 2' to be pulled out from the bottom, having same finish as the shelf. The approved shade/make 1.00mm thick laminate shall be fixed all exposed portions of the shelf, stool etc. complete as per instructions of the Architect.	1.00		No.	
15	SERVER TABLE with Tempered Glass Top - Table Size: - 4'-0" X 2'-0" with drawers on the sides Providing & Fixing table with drawers on either sides made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table shall be 2'-6". The counter top to have 8mm thick tempered/toughened transparent glass, cut to size with edge rounding of all edges, including that on the side table. Depth of the table shall be 2'-6", and shall be fixed with a 4" drawer spanning the 10" width of the table on both sides and matching table depth. The sides and modesty panel with footrest to be made of matching ply and finished with approved shade/ make/ laminate as per Banks Standard Design.	1.00		No.	
Total for Furnishing Works					

ABSTRACT OF COST FOR PROPOSED ELECTRICAL WORK FOR CENTRAL BANK OF INDIA PREMISES FOR RAJAMPET BRANCH					
ELECTRICAL WORK					
Sl.No	Description Of Work	Qty	Rate	Unit	Amount (Rs.)
	To ensure that the main supply can be cut-off at the Branch exit with one main switch while supply is continued to Server/ UPS/ Server Acs	Required wiring and points are included in the Bill of Quantities itself.			
	Supply, Installation & Commissioning of the following				
16	POWER DB (6WAY TPN PHASE SEGREGATED DB) Three Phase, Phase SEGREGATED Distribution board with neutral bar, earth bar, cables ties, top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be IP 42 metallic double door with provision of MCB & ELCB etc as required including cutting of wall and plastering the same with neat finish .It comprising as follows:- (Make: MDS/Hager)Incomer : 63A TPN MCBOutgoings:63A DP MCB- 3Nos10-32 A /25/20A SP MCBs- 18Nos	1		Set	
17	TPN MCB DB Supply, erection, testing and commissioning of three phase 8 WAY, TPN MCB DB double door vertical type, IP 42 powder coated for Main DB with: 125A TPN MCCB – 1No as INCOMER 40A TP MCB - 2 Nos & 32 ASPMCB - 6 Nos Including all interconnections & accessories etc	1		1No	
18	C DB(12WAY SPN DB)12 Way SPN Distribution board with neutral bar, earth bar, cables ties, top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be IP 42 metallic double door with provision of MCB&ELCB etc as required including cutting of wall and plastering the same with neat finish. It comprising as follows:- (Make: MDS/Hager) Incomer : 63ADP MCBOutgoings:10A SP MCBs- 10Nos	1		Set	
19	Supply & Installation of the following with the necessary enclosure and adopter boxes if necessary) 63A DP MCB (UPS INPUT /OUTPUT)	1		Set	
20	Supply & Installation of 32A Metal Clad Socket with top in a specified company manufactured box with suitable rating MCB for connecting A/C points	7		Set	
21	LT CABLES Supply & Laying of the following cables in built up trenches, on wall, or in the ground as per the case may be, with proper clamping with necessary fixing materials etc. Installing testing & commissioning of 1100V grade UG cable as per IS 7098/1554 (Finolex/ Universal)3.5Corex 70 Sqmm FRLSH Aluminium Armoured cable (EB main with inverter if required only)	50		Mtr	
22	End Termination of the above cables with proper Glands and Lugs	4		Set	
23	WIRING Light/Fan point wiring with 3 of 1.5 sqmm Finolex FRLSH PVC insulated copper conductor to be laid in 2mm suitable PVC conduit with Bend, Couplings, etc.. And fixing with clamps screws etc. All conduits to be laid above the false ceiling/partition/concealed in the wall etc. Wiring to be connected with supply & Fixing of6A Modular type switch(MK/ROMA) with suitable Modular plate and metal Box a) One light Controlled by One Switch	34		Pts	
24	b) Two light Controlled by One Switch	5		Pts	
25	c) 6A/16A Switch box Sockets in the switch board itself	2		Pts	

26	Supply & Wiring with Flame Retardant Insulated PVC copper wire as per grade IS 994 for Circuits, Computer point, Power points within 2mm thk PVC conduits with necessary accessories and with proper clamps and to be concealed below the false ceiling. It comprises as follows:- a) 3Runs of 2.5Sqmm copper wire in PVC conduit for circuit mains	100		Mtr	
27	b) 3Runs of 2.5Sqmm copper wire in PVC conduit for Power points	100		Mtr	
28	c) 3Runs of 2.5Sqmm copper wire in PVC conduit for computer points	100		Mtr	
29	d) 2Runs of 4Sqmm copper wire+2.5Sqmm copper wire in PVC conduit for AC wiring	100		Mtr	
30	POWER POINT OUTLETS Supply & Installation of 4 Nos of 6A Sockets (UPS Point) controlled by 2Nos 16A Switches with front plate with enclosure and other accessories etc.(MK /ROMA) for all counters, one additional each in BM cabin, Cash Cabin, Server Room and Customer area for display board	11		Set	
31	Supply & Installation of 1Nos of 6A Socket controlled by 1No 6A Switch with front plate with enclosure and other accessories etc..(MK /ROMA) (Raw Power)	11		Set	
32	Supply & Installation of 1Nos of 6A + 16A Socket controlled by 1No 6A Switch with front plate with enclosure and other accessories etc. (MK /ROMA) (Raw Power)	4		Set	
33	LIGHTING FIXTURES Supply, Fixing & Commissioning of Surface mounting type 2x36W LED fitting with Lamps with fixing accessories.,	16		Set	
34	Supply, Fixing & Commissioning of Surface mounting type 18W LED down-lighter fitting with Lamps and other fixing accessories.	8		Set	
35	Supply & Fixing of exhaust fan dia 9" and Elec Room and toilets - Crompton make	3		Set	
36	Supply & Fixing of ceiling fan dia 30" in Strong room Lockers and dia 24" in cash safe - Crompton make	2		Set	
37	Supply & Fixing of all-metal wall-mounted fan dia IN CASH CABIN/CM CABIN/ATM WALL/3 IN CUSTOMER AREA - Almonard make	7		Set	
38	Supply and installation of tube-light fitting with lamp and with necessary fixing accessories etc IN Back Room, Strong Room, Server Room and Electrical Room	8		Set	
39	CHEMICAL EARTHING Providing dedicated earthing with 50mm, 2m long G.I. electrodes, earthing strip/copper conductor of 25 sqmm and other accessories in the pit filled with conduction compound, includes necessary rods, carbon powder, etc. It should be covered with G.I Manhole cover with necessary civil works. etc.	1		Set	
40	Supply & Laying of 10 Sqmm PVC Insulated Multi-strand copper conductor laid in 25mm dia PVC pipe for Dedicated earth leads from the earth electrodes to the UPS system	50		Mtr	
41	Supply & Laying of 8SWG copper wire	50		Mtr	
Total for Electrical works					

ABSTRACT OF COST FOR PROPOSED DATA-CABLING WORK FOR CENTRAL BANK OF INDIA PREMISES FOR RAJAMPET BRANCH					
DATA CABLING WORK					
Sl. No	Description of Work	Qty	Rate	Unit	Amount (Rs.)
42	Supply and laying of E CAT6 Network cable in the Aluminum trunking box.	225		P/Mtr	
43	Supply and fixing of RJ45 Network socket with front plate and base box for computer workstations.(single I/O point)	11		P/No	
44	Supply and fixing of 3 feet patch card (Systimax)	11		P/No	
45	Supply and fixing of 7 feet patch card (Systimax)	11		P/No	
Total for Data Cabling Works					

PRICE BID SUMMARY for renovation of existing PREMISES FOR RAJAMPET BRANCH

S.No.	Description of item	Amount (Rs.)
1	Furnishing work	
2	Electrical Work	
3	Data cabling work	
Total in figures (excluding GST)		
Total in words (excluding GST)		