

| PRICE BID | | | | | |
|-----------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|----------|-------------|
| ABSTRACT OF COST FOR PROPOSED INTERIOR WORK FOR CENTRAL BANK OF INDIA PREMISES FOR RAYACHOTY BRANCH | | | | | |
| FURNISHING WORK | | | | | |
| Sl. No | Description of Item | Qty. | Rate | Per Unit | Amount (Rs) |
| 1 | <p>COUNTER WITH SIDE TABLE With Tempered Glass Top Size: - 5'-0" X 2'-6" Side Table Size: - 2'-6" X 1'-6" Providing & Fixing officer table & side table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table including side table shall be 2'-6". Depth of the table shall be 2'-6" & side table shall be 1'-6". The counter top to have 8mm thick tempered/toughened transparent glass, cut to size with edge rounding of all edges, including that on the side table. The counter top to have a 12mmthk PLAIN glass partition of 18" height, positioned 6" from Customer side of the Table Top. The top of glass to be straight cut and to have cut-out for transactions with Garware Film (Ice Dot) (Basic Cost Of Film Rs.36/- Per sqft) fixed (at one inch from cut-out edge) as a border to semi-circular cut-out and top. The table shall have one drawer for key board at the corner of the table & side table. The luding all interconnections & accessories etc with additional phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303 finished with approved shade / make/laminate as per Banks Standard Design. Side table to have 2 Drawers at the top and 1 open-able shelf at the bottom. All the exposed surfaces of the table & side table shall be finished in 1.00mm thick approved colour laminate for vertical surfaces and 1.5mm thk approved colour laminate for horizontal surfaces, made Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303 framework tapered box finish, Foot Rest with Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Architect. All exposed surfaces including working TOP of counter shall have decorative laminate. All exposed surfaces shall have 1.00mm thk approved colour laminate in two shades for vertical surfaces & approved colour 1.5mm thick laminate for horizontal surfaces. The internal surfaces shall have same finish including approved Single Lock for Drawer Units, approved Stainless Steel Brush Finish Handles, and approved Brass Powder Coated Wire Manager, Twin Type Telescopic Drawer Channels, Footrest with Rubber Matting etc. complete as per instructions of Architect. The rates shall be inclusive of making of the opening for the Electrical / Computer Wires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots. e Electrical / Computer Wires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots.</p> | 4.00 | | Nos | |
| 2 | <p>CASH COUNTER Table With Tempered Glass Top Size: - 7'-0" X 2'-6" Side Table Size: - 3'-9" X 1'-6" Do as above ITEM NO.A01, but cash counter shall have 3'-0" height for customer top finish with 18" wide 20mm thick ruby red granite top, with 4" overhang on customer side, having 12mm thk PLAIN glass with Garware Film (Ice Dot) (Basic Cost Of Film Rs.36/- per sqft) fixed between 3'-0" & 7'-0" in height with necessary cut-outs etc. complete as per instructions of Architect. Top covered with Aluminium Grill for safety and voucher tray to be provided on adjacent cubicle side of side partition as per site conditions. Side table to have 2 Drawers with currency dividers at the top and 1 open-able shelf at the bottom. All the exposed surfaces of the table & side table shall be finished in 1.00mm thick approved colour laminate for vertical surfaces and 1.5mm thk approved colour laminate for horizontal surfaces, made Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303 framework tapered box finish, Foot Rest luding all interconnections & accessories etc 5-1982) is then screw fixed to ceiling section with 25mm drywait at 230mm centers. Screw fixing is done mechanically either with screwdriver of drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look, which includes filling with CRACK SEAL / tape & finishing the tapered & square edges of theboards with jointing compound, paper tape & two coats of primer suitable for Gypboard. Rate includes provision for recessed/dropped portion in the ceiling with necessary provision for concealed optical fibre lighting as per design specified by architect Note: - For light fittings, grills diffusers and cut-outs, speakers, fire detectors etc. have to be made with the frame of perimeter channels of size 20 X 27 X 30mm X0.545mm thick, supported suitably as per direction of Architect, Electric or A.C. Consultants & shown as per detail drawing without additional payments. Entire false ceiling shall be finish with 3 coats of ICI. Plastic Emulsion paint with necessary scraping, patti, levelling & smooth finish with scaffolding, cleaning etc. Note:- Area of the False Ceiling will be measured in plan i.e. wall to wall. Note: - Existing false ceiling should be removed without any extra charge by the Contractor and carefully stacked as directed / taken out from site.h Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Architect.</p> | 1.00 | | NO. | |

| | | | | | |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--|-----|--|
| 3 | <p>BRANCH MANAGER TABLE WITH SIDE TABLE Table Size: - 6'-0" X 3'-0" Side Table Size: - 3'-0" X 1'-6" With Tempered Glass Top Providing & Fixing Branch Manager table & side table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table including side table shall be 2'-6". Depth of the table shall be 3'-0" & side table shall be 1'-6". The counter top to have 8mm thick tempered/toughened transparent glass, cut to size with edge rounding of all edges, including that on the side table. The table shall have one drawer for key board at the corner of the table & side table. The counter top to have 8mm thick tempered/toughened transparent glass, cut to size with edge rounding of all edges, including that on the side table. The 1'-6" wide side-unit to have two drawers and one shutter below the drawers at the side of the table. The front apron shall be made of Phenol bonded, water proof (BWP) 12mm thk all interconnections & accessories etc 5-1982) is then screw fixed to ceiling to ceiling section with 25mm drywall at 230mm centers. Screw fixing is done mechanically either with screwdriver or drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look, which includes filling with CRACK SEAL / tape & finishing the tapered & square edges of theboards with jointing compound, paper tape & two coats of primer suitable for Gypboard. Rate includes provision for recessed/dropped portion in the ceiling with necessary provision for concealed optical fibre lighting as per design specified by architect</p> <p>Note: - For light fittings, grills diffusers and cut-outs, speakers, fire detectors etc. have to be made with the frame of perimeter channels of size 20 X 27 X 30mm X 0.545mm thick, supported suitably as per direction of Architect, Electric or A.C. Consultants & shown as per detail drawing without additional payments. Entire false ceiling shall be finish with 3 coats of ICI. Plastic Emulsion paint with necessary scraping, patti, levelling & smooth finish with scaffolding, cleaning etc. Note:- Area of the False Ceiling will be measured in plan i.e. wall to wall. Note: - Existing false ceiling should be removed without any extra charge by the Contractor and carefully stacked as directed / taken out from site.h Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Arc</p> | 1.00 | | No. | |
| 4 | <p>FIRE-RATED FULL HEIGHT PARTITION - upto 8'6" for ELECTRICAL ROOM including Fire-rated Door Supply and installation of Bison Panel (cement bonded particle board) with Fire rating of 240 hrs with required components such a Rockwool tight puff, supporting studs and additional fitments, finished on both sides with laminate as per above items with provision of fire-rated door of 3' x 7' with necessary fittings with louvers at the bottom for air circulation</p> | 70.00 | | sft | |
| 5 | <p>LOW HEIGHT PARTITION - 4'0" HEIGHT Do as above (Both Side Laminate Finish), but partition upto 4' height with top of Wood MOULDINGS finish with FRENCH polish etc. complete as per instructions of the Architect.</p> | 64.00 | | sft | |
| 6 | <p>LOW HEIGHT STORAGE - upto 2'6" height behind counters and BM table- Laminate Finish - Providing & Erecting low height storage 1'-6" deep. The top, sides, drawers, sliding shutters / folding shutters and shelves shall be made out of 18mm thk Commercial ply (MR grade) IS303 with C.P.T. Wood frame work. All exposed surfaces finished with 1.00mm thick laminate of approved shade from outside & similar finish on the inside including Brass fittings and Fixtures, Stainless Steel Brush Finish Handles, 6" Tower Bolts, Box Hinges, Shelves at 1'-6" c/c with drawer below as shown in the detail drawing & instructions of the Architect.</p> | 16.25 | | sft | |
| 7 | <p>WALL/COLUMN PANELLING upto 8'6" height - Laminate Finish Providing & Erecting in position approx 8'-6" height or as per the actual sitecondition partitions to be made out of 2" X 2" G.I. sectional frame work 1'-6" / 2'-0" c/c both ways with proper joinery finished with 9mm thk Commercial ply (MR grade) IS303 covering on both sides finished with approved color 1.00mm thk laminate on the outside, complete with wherever support is required, G.I. Sections shall be rigidly fixed to the existing Ceiling, Floors, Beams, Doors & the Side Walls, whichever is applicable, as per instructions of Architect</p> | 187.00 | | sft | |
| 8 | <p>BOTH SIDE LAMINATE DOOR WITH DOOR FRAME - Providing & fixing both side laminate door including door frame made out of 4" X 2 1/2" C.P.T. Wood frame fixed as per required position including shutters made out of 4" X 1 1/2" teak wood frame all round with 6" X 1 1/2" panel at 3'-0" in height including 2" X 1 1/2" brass at 1'-6" c/c both ways. 6mm thk Commercial ply (MR grade) IS303 covering on both sides finish with approved colour 1.00mm thk laminate including frame work of approved shade / make along with PUNIT or SHALIMAR make Heavy Brass Hinges, Brush Finish Stainless Steel Handles, door stopper, door closure, powder-coated Tower Bolts, etc. complete as per the instructions of Architect.</p> | 105.00 | | sft | |
| 9 | <p>WICKET GATE - 3'0" x 3'0" Laminate Finish Providing & fixing both side laminate wicket door fixed as per required position including shutters made out of 4" X 1 1/2" teak wood frame all round with 6" X 1 1/2" panel, top to be flushed with 4'-0" at (low-partition top). 6mm thk Commercial ply (MR grade) IS303 covering on both sides finish with approved colour 1.00mm thk laminate including frame work of approved shade / make along with PUNIT or SHALIMAR make Heavy Brass Hinges, Brush Finish Stainless Steel Handles, door stopper, powder-coated Tower Bolts, etc. complete as per the instructions of Architect.</p> | 48 | | SFT | |

| | | | | | |
|-----------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--|-----|--|
| 10 | <p>GYPSUM / HILUX FALSE CEILING WITH PAINTING at 8'6" ht from finished floor level - Providing & Fixing suspended Gypsum / Hilux Board Grid with PoP ceiling combination false ceiling including recess/drop as per Architect design/detail drawing, which includes providing & fixing G.I. Perimeter channels of size 0.55mm thick having one flange of 20mm & another flange of 30mm & a web of 27mm along with perimeter of ceiling screw fixed to brick wall / partition with the help of nylon sleeves and screws at 600mm centers then suspending G.I. Intermediate channels of size 45mm X 0.9mm thick with 2 flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25 X 10mm X 0.55mm thick fixed to soffit with G.I. & steel expansion fasteners. Ceiling section of 0.55mm thickness having knurled verb of 51.5mm & two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips & in direction perpendicular to the intermediate channel at 457mm centers. 12. Sliding all interconnections & accessories etc 5-1982) is then screw fixed to ceiling to ceiling section with 25mm drywall at 230mm centers. Screw fixing is done mechanically either with screwdriver of drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look, which includes filling with CRACK SEAL / tape & finishing the tapered & square edges of the boards with jointing compound, paper tape & two coats of primer suitable for Gypboard. Rate includes provision for recessed/dropped portion in the ceiling with necessary provision for concealed optical fibre lighting as per design specified by architect Note: - For light fittings, grills diffusers and cut-outs, speakers, fire detectors etc. have to be made with the frame of perimeter channels of size 20 X 27 X 30mm X 0.545mm thick, supported suitably as per direction of Architect, Electric or A.C. Consultants & shown as per detail drawing without additional payments. Entire false ceiling shall be finish with 3 coats of ICI. Plastic Emulsion paint with necessary scraping, patti, levelling & smooth finish with scaffolding, cleaning etc. Note:- Area of the False Ceiling will be measured in plan i.e. wall to wall. Note: - Existing false ceiling should be removed without any extra charge by the Contractor and carefully stacked as directed / taken out from site.</p> | 850.00 | | sft | |
| 11 | <p>NOTICE BOARD - (3'-0" - 2'-0") Providing & Supplying notice board of 3" deep made out of C.P.T. Wood framing with 1/2" Soft Board covered with felt on 6mm thk Commercial ply (MR grade) IS303 for back & glass-shutters fixed with 3" X 1" C.P.T. Wood section finish with 1.00mm thk laminate of approved shade / make with open-able on approved brass hinges with Godrej lock & approved powder coated handle etc. complete as per instructions of Architect.</p> | 1.00 | | NO. | |
| 12 | <p>12mm Thk MAIN GLASS DOOR - 6' wide DOUBLE leaf door WITH FIXED GLASS FOR REMAINING LENGTH ON EITHER SIDE OF ENTRANCE (WHEN FACING BRANCH) - DOUBLE leaf door with required 10mm Thk Fixed Glass with required Boxing all around Providing and Fixing 12mm thick Toughened glass main door with Garware Film (Ice Dot) (Basic Cost Rs.36/-Per SFT) or "V" cut engraving fixed in the frame work along with Brush Finish Stainless Steel 1" Dia 2'-0" Height approved design Handles with 8 Lever Locks, Pull & Push Plate, DORMA make Heavy Duty Floor Spring, etc. complete as per instructions of the Architect.</p> | 154.00 | | sft | |
| 13 | <p>WRITING / CHALLAN DESK - 4'0"x 2'6" Providing & Fixing writing table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. Table shall be fixed at 3'-6". Depth of the table shall be 2'-6". The table shall have 6 compartments for challans of 6" height below the writing surface, as per Banks Standard Design</p> | 1.00 | | No. | |
| 14 | <p>CHEQUE DROP BOX cum SUGGESTION BOX (2'-0" X 1'0") - It shall be made in 18mm thick Commercial ply (MR grade) IS303 frame work with 6mm thick Commercial ply (MR grade) IS303 back 3" X 1" C.P.T. Wood shutters with 6mm thick MODI make with hinges, locks & fixtures. The box to be divided into two portions such that one half serves as drop box, while the other serves as suggestion box, with shorter shutter to leave slot for dropping A4 sized envelope in each box. The approved shade/make 1.00mm thick laminate shall be fixed all exposed portion of the cabinet etc. complete as per site location & instructions of the Architect.</p> | 2.00 | | No. | |
| 15 | <p>MIRROR SHELF - in locker room (7'-0" X 2'0") It shall be made in 18mm thick Commercial ply (MR grade) IS303 frame work with 6mm thick Commercial ply (MR grade) IS303 back 3" X 1" C.P.T. Wooden backing with high quality mirror fixing, with lighting all the top and sides having a cushioned stool of height 2' to be pulled out from the bottom, having same finish as the shelf. The approved shade/make 1.00mm thick laminate shall be fixed all exposed portions of the shelf, stool etc. complete as per instructions of the Architect.</p> | 1.00 | | No. | |
| 16 | <p>SERVER TABLE with Tempered Glass Top - Table Size: - 4'-0" X 2'-0" with drawers on the sides Providing & Fixing table with drawers on either sides made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table shall be 2'-6". The counter top to have 8mm thick tempered/toughened transparent glass, cut to size with edge rounding of all edges, including that on the side table. Depth of the table shall be 2'-6", and shall be fixed with a 4" drawer spanning the 10" width of the table on both sides and matching table depth. The sides and modesty panel with footrest to be made of matching ply and finished with approved shade/ make/ laminate as per Banks Standard Design.</p> | 1.00 | | No. | |
| Total for Furnishing Works | | | | | |

| ABSTRACT OF COST FOR PROPOSED ELECTRICAL WORK FOR CENTRAL BANK OF INDIA PREMISES FOR RAYACHOTY BRANCH | | | | | |
|-------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|------|------|--------------|
| ELECTRICAL WORK | | | | | |
| Sl.No | Description Of Work | Qty | Rate | Unit | Amount (Rs.) |
| | To ensure that the main supply can be cut-off at the Branch exit with one main switch while supply is continued to Server/ UPS/ Server Accs | Required wiring and points are included in the Bill of Quantities itself. | | | |
| | Supply, Installation & Commissioning of the following | | | | |
| 17 | POWER DB (6WAY TPN PHASE SEGREGATED DB) Three Phase, Phase SEGREGATED Distribution board with neutral bar, earth bar, cables ties, top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be IP 42 metallic double door with provision of MCB & ELCB etc as required including cutting of wall and plastering the same with neat finish .It comprising as follows:- (Make: MDS/Hager)Incomer : 63A TPN MCBOutgoings:63A DP MCB-3Nos10-32 A /25/20A SP MCBs- 18Nos | 1 | | Set | |
| 18 | TPN MCB DB Supply, erection, testing and commissioning of three phase 8 WAY, TPN MCB DB double door vertical type, IP 42 powder coated for Main DB with: 125A TPN MCCB – 1No as INCOMER 40A TP MCB - 2 Nos & 32 ASPMCB - 6 Nos Including all interconnections & accessories etc | 1 | | 1No | |
| 19 | C DB(12WAY SPN DB)12 Way SPN Distribution board with neutral bar, earth bar, cables ties, top and bottom removable gland plate and with necessary adopter boxes if any. The DB should be IP 42 metallic double door with provision of MCB&ELCB etc as required including cutting of wall and plastering the same with neat finish. It comprising as follows:- (Make: MDS/Hager) Incomer : 63ADP MCBOutgoings:10A SP MCBs- 10Nos | 1 | | Set | |
| 20 | Supply & Installation of the following with the necessary enclosure and adopter boxes if necessary) 63A DP MCB (UPS INPUT /OUTPUT) | 1 | | Set | |
| 21 | Supply & Installation of 32A Metal Clad Socket with top in a specified company manufactured box with suitable rating MCB for connecting A/C points | 8 | | Set | |
| 22 | LT CABLES Supply & Laying of the following cables in built up trenches, on wall, or in the ground as per the case may be, with proper clamping with necessary fixing materials etc. Installing testing & commissioning of 1100V grade UG cable as per IS 7098/1554 (Finolex/ Universal)3.5Corex 70 Sqmm FRLSH Aluminium Armoured cable (EB main with inverter if required only) | 50 | | Mtr | |
| 23 | End Termination of the above cables with proper Glands and Lugs | 4 | | Set | |
| 24 | WIRING Light/Fan point wiring with 3 of 1.5 sqmm Finolex FRLSH PVC insulated copper conductor to be laid in 2mm suitable PVC conduit with Bend, Couplings, etc.. And fixing with clamps screws etc. All conduits to be laid above the false ceiling/partition/concealed in the wall etc. Wiring to be connected with supply & Fixing of6A Modular type switch(MK/ROMA) with suitable Modular plate and metal Box a) One light Controlled by One Switch | 34 | | Pts | |
| 25 | b) Two light Controlled by One Switch | 5 | | Pts | |
| 26 | c) 6A/16A Switch box Sockets in the switch board itself | 2 | | Pts | |
| 27 | Supply & Wiring with Flame Retardant Insulated PVC copper wire as per grade IS 994 for Circuits, Computer point, Power points within 2mm thk PVC conduits with necessary accessories and with proper clamps and to be concealed below the false ceiling. It comprises as follows:- a) 3Runs of 2.5Sqmm copper wire in PVC conduit for circuit mains | 100 | | Mtr | |
| 28 | b) 3Runs of 2.5Sqmm copper wire in PVC conduit for Power points | 100 | | Mtr | |
| 29 | c) 3Runs of 2.5Sqmm copper wire in PVC conduit for computer points | 100 | | Mtr | |
| 30 | d) 2Runs of 4Sqmm copper wire+2.5Sqmm copper wire in PVC conduit for AC wiring | 100 | | Mtr | |
| 31 | POWER POINT OUTLETS Supply & Installation of 4 Nos of 6A Sockets (UPS Point) controlled by 2Nos 16A Switches with front plate with enclosure and other accessories etc.(MK /ROMA) for all counters, one additional each in BM cabin, Cash Cabin, Server Room and Customer area for display board | 10 | | Set | |
| 32 | Supply & Installation of 1Nos of 6A Socket controlled by 1No 6A Switch with front plate with enclosure and other accessories etc..(MK /ROMA) (Raw Power) | 10 | | Set | |
| 33 | Supply & Installation of 1Nos of 6A + 16A Socket controlled by 1No 6A Switch with front plate with enclosure and other accessories etc. (MK /ROMA) (Raw Power) | 4 | | Set | |
| 34 | LIGHTING FIXTURES Supply, Fixing & Commissioning of Surface mounting type 2x36W LED fitting with Lamps with fixing accessories. | 15 | | Set | |
| 35 | Supply, Fixing & Commissioning of Surface mounting type 18W LED down-lighter fitting with Lamps and other fixing accessories. | 8 | | Set | |
| 36 | Supply & Fixing of exhaust fan dia 9" and Elec Room and toilets - Crompton make | 3 | | Set | |
| 37 | Supply & Fixing of ceiling fan dia 30" in Strong room Lockers and dia 24" in cash safe - Crompton make | 2 | | Set | |
| 38 | Supply & Fixing of all-metal wall-mounted fan dia IN CASH CABIN/CM CABIN/ATM WALL/3 IN CUSTOMER AREA - Almonard make | 8 | | Set | |
| 39 | Supply and installation of tube-light fitting with lamp and with necessary fixing accessories etc IN Back Room, Strong Room, Server Room and Electrical Room | 8 | | Set | |
| 40 | CHEMICAL EARTHING Providing dedicated earthing with 50mm, 2m long G.I. electrodes, earthing strip/copper conductor of 25 sqmm and other accessories in the pit filled with conduction compound, includes necessary rods, carbon powder, etc. It should be covered with G.I Manhole cover with necessary civil works. etc. | 1 | | Set | |
| 41 | Supply & Laying of 10 Sqmm PVC Insulated Multi-strand copper conductor laid in 25mm dia PVC pipe for Dedicated earth leads from the earth electrodes to the UPS system | 50 | | Mtr | |
| 42 | Supply & Laying of 8SWG copper wire | 50 | | Mtr | |
| | Total for Electrical works | | | | |

| ABSTRACT OF COST FOR PROPOSED DATA-CABLING WORK FOR CENTRAL BANK OF INDIA PREMISES FOR RAYACHOTY BRANCH | | | | | |
|---------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-----|------|-------|--------------|
| DATA CABLING WORK | | | | | |
| Sl. No | Description of Work | Qty | Rate | Unit | Amount (Rs.) |
| 43 | Supply and laying of E CAT6 Network cable in the Aluminum trunking box. | 210 | | P/Mtr | |
| 44 | Supply and fixing of RJ45 Network socket with front plate and base box for computer workstations.(single I/O point) | 10 | | P/No | |
| 45 | Supply and fixing of 3 feet patch card (Systimax) | 10 | | P/No | |
| 46 | Supply and fixing of 7 feet patch card (Systimax) | 10 | | P/No | |
| Total for Data Cabling Works | | | | | |

PRICE BID SUMMARY for renovation of existing PREMISES FOR RAYACHOTY BRANCH

| S.No. | Description of item | Amount (Rs.) |
|-------|----------------------------------|--------------|
| 1 | Furnishing work | |
| 2 | Electrical Work | |
| 3 | Data cabling work | |
| | Total in figures (excluding GST) | |
| | | |
| | Total in words (excluding GST) | |